



U.S. Department of Energy

Energy Efficiency and Renewable Energy

Bringing you a prosperous future where energy is clean, abundant, reliable, and affordable

Wind Energy Program Technology Portfolio



Low Wind Speed Technology Phase I: Clipper Turbine Development Project

Clipper Windpower Technology, Inc.

Project Description: Design studies conducted by the U.S. Department of Energy, its subcontractors, and others have indicated that several new design configurations offer significant opportunities for reducing cost over current wind turbine configurations. These technologies include reduction in the cost of and improvements in the efficiency of the drivetrain; increases in energy capture by increasing rotor diameter; and improved active wind turbine controls. Several techniques can be used to achieve these results. Many, such as decreasing drivetrain weight to make taller towers more cost effective, or advanced rotor designs that decrease loads and allow greater rotor diameter, are interrelated.

This project is developing a new turbine design that incorporates a number of advanced elements. This new design, designated the Clipper C-93 Liberty turbine, uses a highly innovative multiple-drive path gearbox feeding four advanced permanent magnet generators. The multiple-drive path design radically decreases individual gearbox component loads, which reduces gearbox weight and size. The new generators significantly reduce component mass by eliminating much of the copper that would be required for windings in the rotor. The machine will also take advantage of advanced feedback controls to reduce load excursions in turbulent wind conditions and optimize pitch schedules to reduce drivetrain loads and improve energy capture. The new machine, with its 93-meter rotor, 75-meter hub height, and 2.5-MW rating promises to be significantly lighter, less costly, and easier to maintain than other machines in this rating.

Project Type: Prototype Development
Total Project Budget: \$18,955,065
Industry Cost Share: \$9,359,147
DOE Cost Share: \$9,595,918
Planned Project Duration: October 2002–December 2006

Contacts:

NREL/Sandia:

Alan Laxson, NREL
1617 Cole Blvd.
Golden, Colorado 80401
303-384-6944
alan_laxson@nrel.gov

Clipper Windpower Technology, Inc.:

Amir Mikhail, Clipper Windpower Technology, Inc.
6305 Carpinteria Avenue #300
Carpinteria, California 93013-2901
805-690-3275
amikhail@clipperwind.com

Current Status: NREL began field tests on the prototype in 2005.



This Clipper 2.5-MW drivetrain underwent dynamometer testing at the National Wind Technology Center.



Clipper 2.5-MW Liberty Turbine installed in Medicine, Wyoming.

A Strong Portfolio for a Strong America • Energy efficiency and clean, renewable energy will mean a stronger economy, a cleaner environment, and greater energy independence for America. Working with a wide array of state, community, industry, and university partners, the U.S. Department of Energy's Office of Energy Efficiency and Renewable Energy invests in a diverse portfolio of energy technologies.

For more information contact EERE Information Center • 1-877-EERE-INF (1-877-337-3463) • www.eere.energy.gov

Produced for the U.S. Department of Energy by the National Renewable Energy Laboratory, a DOE national laboratory

Printed with a renewable-source ink on paper containing at least 50% wastepaper, including 10% post consumer waste.

DOE/GO-102006-2199
March 2006